



# Areal RF Station

A. Vardanyan, L. Hakobyan, H. Avdishyan,  
H. Davtyan, H. Poladyan

Yerevan 16.07.2013

- The AREAL RF system will consist of 3 RF stations:
- Each RF station has 1 klystron, HV modulator, a low-level RF system, preamplifier and an interlock and control system.
  - 1 station is required for RF Gun
  - 2 (or 1 station) stations – for accelerating section(s) operation
  - LLRF systems which control the amplitude and the phase of the RF
  - RF power 7 MW in peak at 3 GHz
  - Interlock and control system

# The Required Operation Parameters



- Peak power 6 MW
- Gradient 17 MV/m
- RF pulse duration 3.8  $\mu$ s
- Repetition rate 1-2 Hz

# RF Power Source



• Frequency	3	GHz
• RF Pulse Duration	3.8	μs
• Repetition Rate	1-2	Hz
• Cathode Voltage	190 - 200	kV
• Beam Current	95 - 105	A
• HV Pulse Duration	3.8	μs
• RF Peak Power	7	MW

# K211 Klystron Parameters




• Output Power peak	7 MW
• Efficiency	40 %
• Gain (min. dB)	31
• Beam voltage	200 KV
• Beam peak current	92A

# KY211 Klystron Main Parameters



• Water and Air Cooling	For Operate Rate (50Hz)		
• Water flow to body	3.64	l/min	<i>min</i>
• Water flow to collector	20.5	l/min	<i>min</i>
• Resistance of cooling water	50	kOhm cm	<i>min</i>
• Air flow to output window 85	l/min	<i>min</i>	
• Cooling Air pressure	2.1	kg/cm <sup>2</sup>	<i>min</i>


# KY211 Klystron Main Parameters



# Low Level Radio Frequency Control

## Characteristics of Signal/Probes:

- Phase stability 0.1 deg@3GHz
- Amplitude stability 0.1%
- Amplitude dynamic range 40 dB
- Ready to be integrated into the EPICS control system



The LLRF system ordered by I-Tech LIBERA.


## Requirements for the RF control system

- Phase and amplitude stability of the accelerating field during 2  $\mu$ s flat-top RF pulse
  - Field amplitude control 0.1%
  - Phase control 0.1°
- A frequency and phase stable master oscillator for RF reference signals to measure the cavity fields

## The RF control system will provide:

- Remote control for all RF components
- An opportunity to change the necessary parameters such as waveguide tuners, phase shifters, etc.

# Control System Block Scheme Overview



# Master Oscillator


The Master oscillator designed by InWave AG according to our requirements.

- Frequency ports:

– 1x 1Hz	1x 9MHz
– 1x 2Hz	1x 81MHz
– 1x 9MHz	1x 250MHz
– 1x 81MHz	2x 90MHz
– 1x 125MHz	2x 10MHz (Secondary)
– 1x 250MHz	1x 10MHz (main)
– 2x 500MHz	
– 1x 1GHz	
– 2x 3GHz	



# The Measurement Results



The picture describes RMS phase Jitter 6.47 fsec !



# The Location of RF Equipment



- **Modulator (HV pulse power source)**
- **HV pulse modulator**
- **1:18,2 pulse transformer in an oil tank.**
- **The nominal pulse duration is 3.8  $\mu$ s.**
- **Requirements to the flat top ripple**
  - should not exceed  $\pm 1\%$ .
  - The pulse-to-pulse stability better than  $\pm 0.5\%$ .

# Measurements


## K211 Modulator



Amplitude flatness ~ 1.2%

# Measurements

## K211 Modulator



> 200 kV

# Equipment




## LB480A Pulse Profiling USB PowerSensor Specifications


50 MHz to 8 GHz (functional to 10 GHz)  
- 60 dBm to +20 dBm  
1.95% Total Error



# Equipment



Power Meter GUI



Pulse profiling GUI


Power Meter Measurements	10 MHz
Pulse Profiling (standard)	100 kHz
Time resolution	0.1 us
10 % to 90% Rise Time	~100 ns
(-70 to -20 dBm pulse measured @ 4 GHz)	

10 % to 90% Fall Time	~100ns
(-70 to -20 dBm pulse measured @ 4 GHz)	

# Equipment



Power Amplifier output (+24dB Att.)



## TESTREPORT FOR MICROWAVE UNIT

PA3G-142.0000.1



Option : Non

Microwave Unit Ser.No. 002 Test Temperature: 22 °C

Measured with :


Power Meter HP 437B Poersensor HP 8481A

RF-Generator Marconi RF Test Set 6203B

Attenuator 25W 20.2 dB Weinschel Type 35-20-34


INPUT Power dBm	Attenuator dB	Measured Power dBm	Output Power dBm	Gain dB	Supply Voltage V	Current A
11.00	dBm	20.20	14.48	34.68	23.68	
10.00	dBm	20.20	13.80	34.00	24.00	
9.00	dBm	20.20	13.02	33.22	24.22	
8.00	dBm	20.20	12.15	32.35	24.35	
7.00	dBm	20.20	11.25	31.45	24.45	
6.00	dBm	20.20	8.99	29.19	24.19	
5.00	dBm	20.20				
3.00	dBm	20.20	7.00	27.20	24.20	
					12.00	0.7

# Klystron V-A Characteristics




A [A]	V [kV]
33.(3)	81.9
36	92.82
52.2(6)	131.04
66	163.8
69.(3)	174.7
77.(3)	192.9
90.(6)	209.3

# S-parameters




Directional coupler 1		Directional coupler 2	
<b>S11</b>	<b>-17,78 dB</b>	<b>S11</b>	<b>-19,316 dB</b>
<b>S12</b>	<b>-0,615 dB</b>	<b>S12</b>	<b>-0,613 dB</b>
<b>(FW) S14</b>	<b>-76,8 dB</b>	<b>(FW)S14</b>	<b>-76 dB</b>
<b>(REF) S23</b>	<b>-76,8 dB</b>	<b>(REF)S23</b>	<b>-73,2 dB</b>

# TH2436 Modulator V-A Measurements



# TH2436 Modulator V-A Measurements



After  
adjusting  
modulator  
coils we  
get +/- 1%

# Net Stability Measurements




Network  
±2.4V/330V  
0.7%

# Measurements



PS  
 12V out  
 $\pm 380\text{mV}/12\text{V}$   
 1.5%

# Solenoid and Body Thermocouple Calibration




Date of measurement 22.10.2012

# Klystrons Input Resonant Frequency Measurement




t=28°C


**K211**



**YK1110**




# Resonant TM010 mode




$\pi$  – mode

freq. – 2.99646 GHz



6 MW flat-top regime

Cavity parameters for TM 010 resonant mode	
Frequency – $f$ [GHz]	2.99646
Unloaded quality factor – $Q_0$	15292.34
Shunt impedance – $R_{sh} = V^2/(2 P_d)$ [MΩ]	2.1174765
$R_{sh}/Q_0$ [Ω]	138.4665
External quality factor – $Q_e$	15434.52
Loaded quality factor – $Q = (1/Q_0 + 1/Q_e)^{-1}$	7681.55
Coupling factor – $\beta = Q_0/Q_e$	0.99
Natural filling time (loaded/unloaded) – $\tau = 2 Q/(2\pi f)$ [μs]	0.816




A. Tsakanian

# Klystron Start Preparation Works




Stage 1




Presented on 19.09.2012

# Stage 1




2 0 1 3

# Wiring of Subsystems



# Wiring of Subsystems



# Conclusion



- The majority of the tasks defined for our group were performed according to the schedule. The critical issue remains the problem of timing which we plan to solve via simple time delays.
- An important problem we haven't yet paid enough attention to is the automatic synchronization of the laser and RF, which at the first phase we plan to perform manually.
- The analog interlock system is implemented and tested which will protect the accelerator and the RF station.
- An additional digital interlock system for the RF system is required. The Digital Interlock System (based on programmable logic devices) will be implemented after the LINAC first stage completion and upon necessity it can be easily modified during operation.



**Thank You for Attention!!!**